

Municipal Inspections, Inc.
601 East Main St. Box 99
Elko New Market, Minnesota 55054
(952) 461-4777 - FAX: (952) 461-2782
Email: Inspectenm@outlook.com

FURNACE AND A/C REPLACEMENT HANDOUT

قا **Inspection Record card or summary permit sheet** shall be available and shall remain on the job-site until the final inspection has been made.

قا Call (952) 461-4777 to schedule your final inspection. For same day inspection, please call between 8:00 a.m. and 9:00 a.m.

قا **Heating Equipment**

- Listed and installed per manufacturer installation instructions- provide instructions.
- Check clearances to furnace
 - 30" in front
 - 1" sides and back minimum (read installation instructions).
 - 6" to combustibles single wall vent
 - 1" to combustibles Class B vent
- Provide flue gas test (ORSAT) on all heat producing equipment indicating:
 - Carbon monoxide (CO) < 400 parts per million
 - Carbon dioxide (CO²) 6-9%
 - Oxygen (O²) 4-10%
 - Stack temperature = 480° F for metal and = 200° F for plastic

قا **Ducts**

- Check for vibration isolation between duct and furnace on supply and return.
- Check overall tightness of joints for air leakage.

ثفا

Venting

- Every furnace shall be vented to the exterior.
- Check vent connector rise and length to vent. (1/4" per foot min rise 6 feet max)
- Furnace needs to be vented per manufactures installation instructions (read installation instructions).
- Must have roof cap installed on top of flue.
- Must have 3 screws per joint on single wall vent.

ثفب

Combustion Air Supply

- Determine combustion air source. May be installed in the return duct with an undampened opening into the mechanical room. Provide opening on supply plenum not return duct.
- Combustion air must be in the same room as the furnace and water heater.
- Combustion air duct sized at least the same size as the flue and insulated.
- Make sure openings are not blocked or restricted. Minimum 12" above grade level.
- Verify that inlet openings are properly screened 1/4" mesh.
- Verify that duct is R5 insulated.
- Duct needs to be strapped with 1-1/4" wide strapping every 4'. Outlet of duct to be maximum 12" above interior floor but at least 2' from any water main or water pipe to protect from freezing.
- Verify location of inlet on exterior-to-exterior exhaust vents (3'). If the combustion air is in the return, then the separation becomes 10'.