Municipal Inspections, Inc. 601 Main Street Box 99 Elko New Market, MN. 55054 Email: Inspectenm@outlook.com PHONE (952) 461-4777 FAX: (952) 461-2782

GARAGE HEATER HANDOUT

^f**Inspection Record card or summary permit sheet** shall be available and shall remain on the job site until the final inspection has been made.

164 (259) llaC ف-4777 to schedule your final inspection. For same day inspection, please call between 8:00 a.m. – 9:00 a.m.

Heating Equipment ال

- \rightarrow Listed and installed per manufacturer provide instructions.
- \rightarrow Check clearances to furnace.
 - 30" in front
 - 1" sides and back minimum (read installation instructions)
 - 6" to combustibles single wall vent
 - 1" to combustibles Class B vent

 \rightarrow Provide flue gas test (ORSAT) on all heat producing equipment indicating:

•Carbon monoxide (CO)< 400 parts per million

•Carbon dioxide (CO²) 6-9%

•Oxygen (O²) 4-10%

•Stack temperature = 480° F. for metal and = 200° F for plastic

ڤ gnitneV

- \rightarrow Every garage heater that produces products of combustion shall be vented to the exterior.
- \rightarrow Check vent connector rise and length to vent. (1/4" per foot min rise 6 feet max).
- → Furnace needs to be vented per manufactures installation instructions (read installation instructions).

- \rightarrow Must have roof cap installed on top of flue.
- \rightarrow Must have 3 screws per joint on single wall vent.

ف gnipiP saG

- \rightarrow Must have 25# air test for 12 hours on gas line, homeowner or contractor responsible for test equipment.
- → Copper tubing (Type L, K or ACR), iron, galvanized or black steel with threaded fittings or welded pipe.
- \rightarrow Branch lines not connected to appliances must be plugged.
- \rightarrow Check gas lines are not bent, strained or kinked.
- \rightarrow Joints need to be brazed, not soldered. Must use couplings for reducers.
- \rightarrow Strap all gas lines every 6' with copper straps.
- \rightarrow Shutoffs for appliances outside of appliance and within 3'.
- \rightarrow Must have drip-T on gas line.
- → Must have Maxitrol installed horizontal and level with a drip-T before the Maxitrol on the high pressure side.
- \rightarrow Must have shut-off and union on furnace gas supply.